TABLE OF INFILTRATION/STORAGE VAULT ELEVATIONS

STORAGE VAULT	EST. S.H.W.T.	BOTTOM STONE	INVERT OUT	TOP OF CONCRETE
A	57.8	60.00	60.70	62.75
B	49.63	52.00	52.70	54.75
C	52.38	54.50	55.20	57.25
D	60.15	62.15	62.85	64.90
E	58.0 *	60.50 (VAULT E IS STORAGE ONLY)	61.20	63.25

* TO BE CONFIRMED WITH ON-SITE EVALUATION

I HEREBY CERTIFY THAT THIS PLAN CONFORMS TO THE RULES AND REGULATIONS OF THE REGISTERS OF DEEDS OF THE COMMONWEALTH OF MASSACHUSETTS

FOR REGISTRY USE ONLY

TABLE OF RAIN GARDEN ELEVATIONS

RAIN GARDEN	EST. S.H.W.T.	BOTTOM ELEV.	OVERFLOW RIM	OVERFLOW INVERT
1 (2' Depth)	61.47	63.50	66.00	63.00
2 (2' Depth)	53.95	56.50	59.00	56.00
3 (3' Depth)	51.57	54.00	57.50	56.50
4 (2' Depth)	58.08	60.10	62.60	60.00
5 (3' Depth)	60.25	62.25	65.75	63.00
6 (3' Depth)	53.17	60.00	63.50	62.25

NOTE : STRUCTURE 400 IS A FLOW SPLITTER MANHOLE SEE DETAIL ON SHEET 13

RAIN GARDEN No. 3 - 3' Depth
BOTTOM = 54.00
OVERFLOW RIM = 57.50
OVERFLOW INVET = 56.50

Approved by the Topsfield Planning Board

Date Filed

Prepared By:
Eastern Land Survey Assoc., Inc.
Christopher R. Mello P.L.S.
104 Lowell St. Peabody MA 01960
(978) 531-8121

Prepared For
New Meadows Enterprises LLC
30 Wildes Road
Topsfield, MA 01983

SITE DEVELOPMENT PERMIT PLAN
THE MEADOWS
TOPSFIELD, MASSACHUSETTS
DETAIL DEVELOPMENT PLAN

F 14730

SHEET NO.
8 OF 14

SCALE 1" = 20'

DATE: September 2, 2008

REVISIONS
1. MARCH 31, 2009
2. JUNE 1, 2009.
3. JULY 9, 2009
4. SEPTEMBER 16, 2009

Christopher R. Mello PLS 31317

Clayton A. Morin PE 30969